

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, Dekalb, Mississippi, until 10:00 am on the 12th day of June, 2007 and shortly thereafter publicly opened for the construction of 0.263 miles of PRESTRESSED CONCRETE BEAM SPAN BRIDGE & GRAVEL SURFACE APPROACHES on the HOGEYE ROAD being known as Project No. BR-0035(24)BO in Kemper County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
CLEARING AND GRUBBING	0.050	AC
REMOVAL OF BRIDGE (STA. 12+33.98)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	11,256.000	CY
BORROW EXCAVATION (A.H.) (FME) (CONTRACTOR FURNISHED) (CLASS 9)	3,297.000	CY
GRANULAR MATERIAL (LVM) (CLASS 9, GROUP B)	5,295.000	CY
SIZE I STABILIZER AGGREGATE, COARSE (LVM)	562.000	CY
MIXING, SHAPING AND COMPACTION	4,336.000	SY
44" X 27" CONCRETE ARCH PIPE, CLASS A III	48.000	LF
58" X 36" CONCRETE ARCH PIPE, CLASS A III	40.000	LF
44" X 27" CONCRETE ARCH PIPE END SECTION	2.000	EA
58" X 36" CONCRETE ARCH PIPE END SECTION	2.000	EA
GUARD RAIL, W-BEAM, COMPLETE-IN-PLACE	112.500	LF
GUARD RAIL, TYPE I, THRIE-BEAM, BRIDGE END SECTION, COMPLETE-IN- PLACE	4.000	EA
GUARD RAIL (TERMINAL END SECTION)	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	21.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA

SECTION 900  
 PROJECT NO. BR-0035 (24)BO  
 KEMPER COUNTY

---

REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC HAZARD SIGN (ENCAPSULATED LENS)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	8.180	TON
COMMERCIAL FERTILIZER (13-13-13)	4.090	TON
AMMONIUM NITRATE	0.610	TON
SEEDING	4.090	AC
VEGETATIVE MATERIALS FOR MULCH	8.180	TON
SOLID SODDING	1,000.000	SY
PORTLAND CEMENT CONCRETE	98.260	CY
PAVED DITCH		
TEMPORARY EROSION CHECKS	36.000	BL
TEMPORARY SILT FENCE, (TYPE II) (EOS 20-100)	2,480.000	LF
LOOSE RIPRAP, (SIZE 200 LB.)	49.000	TON

BRIDGE ITEMS:

TEST PILES	3.000	EA
LOADING TESTS	0.000	EA
10" STEEL PILING	1,175.000	LF
CLASS "B" BRIDGE CONCRETE	317.080	CY
31' PRESTRESSED CONCRETE BEAM	246.000	LF
40' PRESTRESSED CONCRETE BEAM	795.000	LF
60' PRESTRESSED CONCRETE BEAM	239.000	LF
REINFORCEMENT	66,308.000	LB
CONCRETE RAILING	644.000	LF
LOOSE RIPRAP, (SIZE 300 LB.)	184.000	TON
FILTER FABRIC (TYPE V) (EOS 70-100)	456.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 180 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County, the County Engineer's office and the Office of the State Aid Engineer, 412 Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, County Engineer for Kemper County, Mississippi, 1724B 23RD Avenue, Meridian. The Cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

James E. Granger, President  
Kemper County Board of Supervisors